

BY REGD. POST WITH ACK. DUE IN DUPLICATE



TRANSMISSION CORPORATION OF TELANGANA LIMITED  
VIDYUT SOUDHA :: HYDERABAD – 500 082. Off: PABX:040-23396000  
Website:Transco.telangana.gov.in CIN No:U40102TG2014SGC094248

**From:**  
The Chief Engineer/Transmission  
TSTRANSCO, Vidyut Soudha,  
Hyderabad - 500 082  
Fax No.040-23393453  
**To:**  
M/s.K. K Rao.Engineering Works Pvt Ltd.,  
Plot. No. Part of 8, Road No.1,  
Nacharam,Hyderabad-500 076.  
**P.O.No. 305 /CE(Tr)/SE(Tr)/DE(SS)/ADE1/F.Seetapuram/F.No.5570/17/MC- 08 /D.No. 178 /19,**  
**Dt: 13.03.19.**  
Sir,

**Sub:-** Repair of 1 No. 100 MVA, 220/132KV PTR, T&R make, Sl.No.23001, Y/M: 2009 failed at 220/132KV Seetapuram SS , Nalgonda OMC circle on rate contract basis - Detailed Purchase Order - Issued.

**Ref:-**1) Specification No.TST-01/2017.  
2) Lr.No.CE(Tr)/SE(Tr)/DE(SS)/ADE1/RC:16-17/D.No.113/17/ Dt:28.02.17  
3) Lr.No.CE(Tr)/SE(Tr)/DE(SS)/ADE1/F. Repair RC 2017/D.No.630/18, Dt:30.07.19

>><<

I, acting for and on behalf of and by the order and direction of the Transmission Corporation of Telangana Limited (hereinafter called the 'TSTRANSCO') hereby accept the rates offered by M/s.K.K.Engineering works Pvt. Ltd., (here in after called the Company or the Repairer or the Contractor) as per rate contract (3<sup>rd</sup> cited) for repair of 1 No. of 100 MVA, 220/132KV PTR, T&R make, Sl.No.23001, Y/M: 2009 failed at 220/132KV Seetapuram SS , Nalgonda OMC circle with the following terms and conditions.

**2. SCOPE OF MATERIALS, WORKS & PRICES:** This contract relates to repairs of 1 No. of 100 MVA, 220/132KV PTR, T&R make, Sl.No.23001, Y/M: 2009 failed at 220/132KV Seetapuram SS, Nalgonda OMC circle.

**3. SCHEDULE OF MATERIAL, WORKS, TRANSPORTATION & CREDITS:**

Sl. No.	SAC Code	Description of Work as Specified	Rate Contract Item No.	Units	Quantity	Rate per unit in Rs.	Total Amount in Rs.
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)
A		<b>JOB INVOLVING ONLY LABOUR PORTION</b>					
1	998717	For repair of PTRs: Removal of active parts from tank, cleaning all healthy parts including coils, lamination, tank, tap changer including sleeves and re-assembly of core and winding with old healthy and re-wound coils and other new parts in lieu of damaged one including brazing, soldering, sleeving and insulating etc. as required. Oven drying of assembled core and winding, reassembly of Transformer by tanking the dried core and winding assembly, fixing of all oil valves, fitting of accessories, making of terminal connections to external bushings, including routine tests on PTR as per IS:2026.	1	LS	1	1080000.00	1080000.00

Sl. No.	SAC Code	Description of Work as Specified	Rate Contract Item No.	Units	Quantity	Rate per unit in Rs.	Total Amount in Rs.
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)
2	998717	Labour charges for Overhauling of Radiators by providing new Drain plug and Teflon washers	7	Nos.	10	2140.00	21400.00
3		Labour Charges for Winding coils with new winding wire and new insulation	9				
a	998717	HV Tap Winding (For Y Phase)	a	Kgs	3220	173.00	557060.00
b	998717	HV Tap Winding (CTC) (For Y Phase)	d	Kgs	1380	214.00	295320.00
4	998717	Labour charges for overhauling of existing OLTC, including Drive Mechanism along with replacement of damaged parts.	12	Set	1	48150.00	48150.00
5	998717	Filtration of new oil and filling.	21	KL	51.065	2675.00	136598.88
6	998717	Filling of Power Transformer with Nitrogen gas with a pressure of 0.4 Kgs per Sq.cm	23	Each PTR	1	21400.00	21400.00
		Sub Total-A					2159915.50
<b>B</b>	<b>HSN Code</b>	<b>JOB INVOLVING ONLY MATERIAL PORTION</b>					
7	7408	Supply of new copper winding wire for HV Y-Phase	1	Kgs	3220	466.80	1503096.00
		Supply of new paper insulation	2				0.00
8	7409	Supply of new CTC Conductor for Tap winding.		Kgs	1380	666.61	919921.80
9	8404	Supply of Buchholtz relay	21	Each	1	3809.18	3809.18
10	8404	Supply of Dial type Thermometer (Winding) with 2/4 contacts	23	Each	1	10680.00	10679.96
11	8514	Supply of breather with Silica gel for Main tank	24	Each	1	4761.48	4761.48
12	8514	Supply of breather with Silica gel for OLTC	25	Each	1	4280.88	4280.88
		Sub total-B					2446549.30

Contd ..3

Sl. No.	SAC Code	Description of Work as Specified	Rate Contract Item No.	Units	Quantity	Rate per unit in Rs.	Total Amount in Rs.
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)
<b>C</b>	<b>HSN Code</b>	<b>JOB INVOLVING MATERIAL &amp; LABOUR PORTION.</b>					
13	8504	Complete spray of Transformer tank externally with 2 coats of enamel paint (with material)	3	L S }	1	50471.7	50471.7
		Painting of Transformer tank internally with Oil resistant paint with 2 coats					
14	8504	Providing/changing of all gaskets	7	LS	1	29903.9	29903.88
15	8504	Providing new insulation for leads (phase and Neutral) Tap leads, inter winding connections and inter coil connections.	8	LS	1	57137.8	57137.77
16	8504	Providing new Insulation for the existing Tap Leads	9	Each	42	1333.21	55994.82
17	8504	Providing HV static rings including new insulation	11	Each	2	14284.4	28568.88
18	8504	Providing of New FCC for 10 fans	27	LS	1	85706.7	85706.66
		Sub-Total-C					307783.71
<b>D</b>		<b>TRANSPORTATION</b>					
19	8709	Transportation of PTR main tank, weighing above 70MT and up to 90MT on hydraulic trailer from 220 KV Seetapuram SS to M/s K.K Rao Engg Pvt Ltd, factory site, Hyderabad)	1.c	MT/ KM	Rs.30.24 Subject to a minimum of Rs.5,14,500/- Per Movement	82.5MT/ 210KM	523908.00
20	8709	Return Transportation of PTR Main tank, weighing above 70MT and up to 90MT on hydraulic trailer from M/s K.K Rao Repair Bay to allotted site (As per Actuals)	c	MT/ KM	Rs.30.24 Subject to a minimum of Rs.5,14,500/- Per Movement	514500 82.5MT 206 KM	514500.00
21	8709	Transportation of accessories through lorries excluding transit insurance from 220 KV Seetapuram SS to M/s K.K Rao Engg Pvt Ltd, Hyderabad).	3	MT/ KM	Rs.5.78 subjected to min. Rs5250/-	10 T/ 210 KM	12138.00
22	8709	Transportation of accessories through lorries excluding transit insurance from M/s K.K Rao Engg Pvt Ltd, Hyderabad to allotted site. (As per actuals)	3	MT/ KM	Rs.5.78 subjected to min. Rs5250/-	10T/ 200 KM	11560.00
23	8709	Transportation of oil barrels by engaging 7 Nos. lorries from TLC stores Erragadda, Hyderabad to M/sK.K.Rao Engineering Pvt Ltd, Nacharam, Hyderabad including loading and unloading of barrels	4	per lorry	7	5250.00	36750.00
		Sub-Total-D					1098856.00

Contd—4

24		Transit Insurance for transporting 100MVA PTR from Seetapuram SS to M/s K.K Rao Engineering Pvt Ltd,Hyderabad.					25000.00
25		Transit Insurance for transporting 100 MVA PTR from works site to allotted SS after carrying out repairs (As per actuals)					25000.00
E		Grand Total Amount (Sub-Total A+B+C+D)					6013104.51
F		GST @ 18% on Sl. No. E					1082358.81
G		Gross total with GST including Transit insurance to & fro (Sl. No. E+F)					7145463.32
H		Less credits (H)					1217927.08
I		Net Total (I) = (G)-(H)					5927536.24
		say					5927537.00
		(Rupees Fifty Nine Lakhs Twenty Seven Thousand Five Hundred and Thirty Seven only)					
Sl. No.	SAC Code	Description of Work as Specified	Rate Contract Item No.	Units	Quantity	Rate per unit in Rs.	Total Amount in Rs.
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)
H	HSN Code	CREDIT FOR PARTS					
26	7404	Damaged HV/LV Coils	2	Kgs	2737	233.4	638815.8
27	7404	Damaged HV Tap Coil CTC	2	Kgs	1173	333.31	390972.63
28	7404	Buchholtz relay scrap	10	Each	1	380.918	380.92
29	7404	Dial type Thermameter (winding) with 2/4 contacts scrap	10	Each	1	1068.00	1068.00
30	7404	Breather with Silicagel for main tank scrap	10	Each	1	476.148	476.15
31	7404	Breather with Silicagel for OLTC scrap	10	Each	1	428.088	428.09
32		Total Less Credits					1032141.59
33		Add GST @18% on Sl. No. 32					185785.49
		Total with GST (Sl. No. 31+32)					1217927.08
(H)		Sub Total:H					1217927.08

**Note:** Devolution of Empty Transformer oil barrels shall be arranged by the concerned Superintending Engineer, to nearest TLC Stores of TSTRANSCO departmentally or credit shall be given by the above repairer for retaining them as per the latest sale price of TLC Stores, Erragadda, Hyderabad. Other parts not shown as credits shall be devoluted to nearest TLC Stores of TSTRANSCO departmentally.

**4. PRICES:** The above prices are firm and inclusive of packing and forwarding charges. The repairer shall not be eligible for any extra charges in respect of minor accessories even though they are not mentioned. All other parts, which are not shown at credits, are to be devoluted to TLC Stores. Loading & unloading of the PTR has to be attended by the repairer, at their work shop without any extra cost.

5. **TAXES AND DUTIES:** The above prices are inclusive of:

a. (i) GST @ 18%

b) **TAX RECOVERIES:**

i) The GST (Goods and Service Tax) @ 18% shall be collected from the Repairer on the credits i.e H towards removed parts retained by the repairer and the same may be intimated to the Executive Director/Finance, Vidyuth Soudha, TSTRANSCO, (against the GST No. 36AAFCT0166J1Z9) for remittance by Executive Director/Finance.

ii) Labour Cess @ 1% on total amount of the Schedule-A, Schedule-C & Schedule-D shall be collected from the repairer

iii) GST-TDS @ 2 % on the amount of work exclusive of GST shall be collected from the repairer and the same shall be remitted to the concerned Tax department.

6. **FREIGHT AND INSURANCE:**

i) The above prices are inclusive of Freight and Insurance charges for transporting of the Power Transformer from site to the works (to & fro) of the repairer, for repairs.

ii) The above Power Transformer including oil and all accessories are to be transported to the allotted Substation through Hydraulic trailer after repairs at a minimum cost of Rs.2,62,500.00 excluding return Transit insurance and Taxes.

iii) The repair bills including the return transportation charges as per actuals with return Transit insurance & Taxes from works site to the allotted EHT Substation at approved rates shall be submitted to the Superintending Engineer/OMC/Nalgonda for arranging payment. The concerned SE/OMC to whom the PTR allotted is authorized to finalize the return transportation mileage.

iv) Arranging the insurance shall be responsibility of the repairer. The Insurance policy shall cover the period of repairs and storage for 60 days after repairs at site. The policy taken should contain a provision for extension to cover further storage and erection at TSTRANSCO's cost.

7. **TERMS OF PAYMENT:**

i) 100% payment shall be paid within 45 days after receipt of the repaired Power Transformer in good condition duly certified by the consignee at allotted sub-station subject to **Clause 10 i.e. PERFORMANCE GUARANTEE** of this purchase order.

ii) Payments shall be made by the Cheque / by way of Electronic Fund Transfer / RTGS from TSTRANSCO funds.

Bank account details for payment through RTGS system:

Bank Account Name	:	M/s.K.K.Rao, Engineering Work Pvt. Hyderabad.
Name of the Bank	:	Andhra Bank
Name of the Branch	:	SME Branch,Nacharam
Branch Code	:	1031
City	:	Hyderabad
Account No.	:	103113100000089
MICR No.	:	500011053
IFSC No.	:	ANDB0000873

iii) The payment of the repair bill shall be admitted only on certifying the aspect of carrying out five stage inspections as per **Clause 11 i.e. STAGE INSPECTION** of the Purchase Order. The certificate shall be issued by the concerned SE/OMC, where PTR shall be re-allotted after repairs by the company.

## **8. GUARANTEE:**

i) The Company shall give performance guarantee for the materials replaced/rectified by you for a total period of **36 months** of service from the date of commissioning of the repaired power transformer.

ii) In case, the repaired PTR fails **within 36 months** of guarantee period mentioned in clause (i) above, the repaired PTR should be guaranteed for a total period of **42 months** from the date of first commissioning after repairs, on the portion of repairs attended by the repairer and performance Bank Guarantee shall be extended accordingly.

iii) The company shall rectify thermal faults, attend oil leakages, problems of high operating winding & oil temperatures, problem of increasing dissolved gases etc., if any observed in the repaired PTR up to **36 months (i.e. within guarantee period)** from the date of commissioning of the repaired PTR, after repairs. The rectified PTR should be guaranteed for a total period of **42 months** from the date of commissioning after repairs, on the portion of repairs attended by you and performance Bank Guarantee shall be extended accordingly.

iv) If the repairer fails to respond to the intimation of TSTRANSCO **within 1 week**, to attend the defects during Guarantee period, TSTRANSCO shall arrange for rectification of the defects through any other agency at the cost and risk of the repairer and recover the cost of rectification from pending Bills/ Bank Guarantees of the repairer.

v) To & fro transportation and repair cost of failed PTR during guarantee period has to be borne by the repairer.

## **9. SECURITY DEPOSIT :**

i) The Security Deposit (SD) of Rs.2.50 lakhs in the form of Bank Guarantee has to be submitted by the repairer within 15 days from the date of receipt of purchase order for repair of PTR. This is in addition to the performance guarantee. The Bank Guarantee shall be valid for a period of **two years** and with a claim period of six months thereafter. The Bank Guarantee has to be extended in case of extension of completion period of repair. This will not be waived, in any case, under any circumstances. The amount shall be forfeited, if the repairer fails to fulfill the terms of contract / order.

ii) Manufactures registered as SSI Units with Industries Department, Government of Telangana State are not exempted from payment of SD, as the repair work is not considered as a supply item.

**10. PERFORMANCE GUARANTEE:** The Company shall furnish performance Bank Guarantee (PSBG) for 5% total value, including all taxes and return transportation charges on Rs.100/- Non-judicial stamp paper covering the period of **36 months** guarantee plus **six months** claim period over and above the guarantee period before payment becomes due. In absence of performance Bank Guarantee, only 95% of the bills shall be processed initially and balance 5% shall be paid after completion of the guarantee period i.e., 42 months from the date of commissioning of repaired PTR.

**11. STAGE INSPECTION:**  
a. RAW MATERIAL INSPECTION

The Repairer shall invariably use the Copper, CRGO laminations and Insulating Paper from any of the vendors listed below, as per the Clause No.3 (d) of Section –I, i.e General of Technical Specification 1<sup>st</sup> cited.

Sl. No.	Name of the material	Make/IS Standard	Source of Supply
(i)	Winding wire (Copper strip/ Conductors)	1.Hindalco Ltd 2.Sterilite Ltd 3.Any of PGCIL Approved Make 4.Any of TSTRANSCO approved Make	
(ii)	Core lamination (CRGO)	1.A.K Steel 2.Nippon Steel 3.JFE Steel/Posco 4. Any of PGCIL approved make 5.Any of TSTRANSCO approved make	
(iii)	Insulation paper	1.H.Weidmann 2.Munksio 3.Krammer 4.Dupont 5. Elof Hansen 6. Any of PGCIL approved Make 7. Any of TSTRANSCO Approved make.	

However, the procured raw material should be offered for stage inspection, before utilizing for the repairs. The Repairer shall furnish copies of evidence of procurement of raw materials from vendors as in Clause No. 3(d) of Section –I i.e., General (Copies of Invoice, necessary link documents, if any, Manufacturers test reports shall submitted to the Chief Engineer/Transmission/Vidyut Soudha/Hyderabad for issue of Utilization clearance on the Material.)

b. The Company shall offer five stage inspections as follows during the repairs of the Power Transformer, in addition to the final testing.

Sl. No.	Stage No.	Works to be covered
(i)	1 <sup>st</sup> stage	Formation/ Rewinding of LV coils/ Tertiary winding and insulation
(ii)	2 <sup>nd</sup> stage	Formation/ Rewinding of HV coils and insulation
(iii)	3 <sup>rd</sup> stage	Formation/ Rewinding of Tap winding and core fixation
(iv)	4 <sup>th</sup> stage	To ensure all the works attended as per the Joint Inspection Report and repair estimate/PO. Inner and outer sides painting of Power Transformer and pressure test on PRV.
(v)	5 <sup>th</sup> stage	Oil filling and complete assembly and accessories. Leak test on Radiators, leak test on Main Tank (if any modifications carried out on main tank) etc.,

The inspection reports shall be submitted to the CE/Transmission/TSTRANSCO. All items covered under **Clause 3 i.e. SCHEDULE OF MATERIAL, WORKS & PRICES** of this order shall cover in Stage inspections.



12. **PHOTOGRAPHS:** The repairer shall submit the photographs of the damaged parts observed in the allotted sick Power Transformer during the Joint Inspection. Further, the photographs of the replaced parts taken at every stage inspection shall be submitted along with Stage Inspection Reports.

13. **INSPECTION:** The Company have to intimate this office at least 15 days in advance, as and when propose to conduct the tests, for deputing TSTRANSCO's representative to witness the tests. Final Inspection (Test) reports shall be submitted, duly entering Minutes of Meeting (MOM) indicating the tests conducted, comments on Test results and any balance works to be attended. Without the MOM by the inspecting officer, the Test reports shall not be considered for approval and issue of dispatch instructions. Three copies of the test certificates containing results of all tests carried out, shall be submitted to the Chief Engineer/Transmission, for approval, before the equipment is going to be dispatched. The final testing of the Power Transformer after repairs shall be conducted, duly assembling the radiators, conservator tank and filling the total quantity of Transformer oil.

14. **TEST AND TEST CERTIFICATES:** All the routine tests in accordance with relevant ISS/BIS/IS-2026 shall be carried out on the equipment in the presence of TSTRANSCO's Engineer. Three copies of the test certificates shall be furnished to this office immediately, after the tests and get them approved before payment becomes due. The equipment shall not be dispatched without obtaining the approval for test certificates.

15. **COMPLETION PERIOD:**

i) The repair of the Power Transformer shall be completed within **Nine** months from the date of receipt of Purchase Order. However, the company is requested to advance the repairs and complete the same **within 6 months**, in view of the urgent requirement of Power Transformers.

ii) In case, if the repaired PTR fails within guarantee period of **36 months** from the date of its commissioning, the failed PTR shall be repaired / rectified and delivered to allotted site by the Repairer at free of cost **within 3 months** from the date of written intimation of such failure, failing which the cost of the repairs incurred will be deducted from the bills.

16. **PACKING:** The Supplier/Manufacturer/Repairer shall provide such packing for the material/equipment as is required to prevent their damage or deterioration during transit to their final destination, as indicated in the Technical Specification for material / equipment. The packing shall be sufficient to withstand, without limitation, rough handling during transit and exposure to extreme temperatures, humidity etc. during transit and open storage.

17. **DESPATCH INSTRUCTIONS:-** The dispatch instructions shall be communicated separately, after completion of repairs, successful completion of testing and approval of Test certificates considering **Clause 13 i.e. INSPECTION**.

18. **UNDERTAKING:** The Repairer should furnish an undertaking as per Schedule-XV of Specification 1<sup>st</sup> cited with reference to the welding, oil filtration, Faults, Materials being used, stage Inspections (4<sup>th</sup> and 5<sup>th</sup> stage) and etc.,

19. **ADDITIONAL NAME PLATE:** Immediately after completion of repairs and test, the repairer shall affix on the Transformers, just below the manufacturers name plate (Metallic) / any suitable place of suitable size with the following details punched on it:

- (i) Name of the Repairer:-
- (ii) Tested on:
- (iii) Delivered on:
- (iv) Purchase Order No:



**20. PENALTY FOR LATE DELIVERY:** The time for and the dates for delivery mentioned in the repair order shall be deemed to be the essence of the contract. In case of delay, in delivery of equipment/repair of PTR/Transport of PTR to destination, whatever be the reason, the TSTRANSCO may at its option, demand and recover from the Repairer an amount equivalent to **half percent of the value of the contract for every week of delay or part thereof, subject to a maximum of 5% of the total value of the contract (Net value).** This right under the law including the right to cancel the contract, forfeit the deposit and /or recover damages for breach of the Contract.

- i) The date of receipt of the equipment/materials at the destination in good condition will be taken as the date of delivery.
- ii) For penalty, the number of days of delay would be rounded off to the nearest week and calculated accordingly.
- iii) Materials/ Equipment, which are not of acceptable quality or not conforming to the Specification would be deemed to be not delivered.
- iv) The date of receipt of the last component of the Transformer shall be reckoned as the date of delivery for the purpose of calculation of penalty for delay in delivery.

**21. FORCE MAJEURE:** The Repairer shall not be liable for delay or for failing to supply the material / equipment for reasons of 'Force Majeure' such as acts of God, acts of Public enemy, acts of Government, fires, floods, strikes, lockouts strikes and etc., in works of manufacturers of proprietary items as specified by the TSTRANSCO.

The contractor shall within 10 days from the beginning of such delay notify to the TSTRANSCO in writing the cause of delay. The TSTRANSCO shall verify the facts and grant such as extension of time as facts justify.

**22. LOSS (or) DAMAGE:** The Repairer is responsible for the safe custody of Power Transformer during the repairs and delivery of the repaired Power Transformers, in good condition, at the destination. The Repairer should acquaint themselves of the conditions, for handling and transporting of the Power Transformer to the destination. The company shall include and provide the security and protective packing of the goods, so as to avoid damage in transit.

External damages or shortages that are prima-facie the results of rough handling in transit or due to defective packing will be intimated within a fortnight of the receipt of the equipment/materials. Internal defects, damages or shortages of any integral parts which cannot ordinarily be detected on a superficial visual examination though due to bad handling in transit or defective packing will be intimated within 2 months from the date of receipt of the equipment/materials. In either case, the defective or damaged equipment/ materials should be replaced by the contractor free of cost to the TSTRANSCO. If no steps are taken within 15 days of receipt of intimation of defects or such other reasonable time, as the TSTRANSCO may deem proper to afford, the TSTRANSCO may without prejudice to its other rights and remedies cause to be repaired or rectified the defective material or replace the same and recover the expenditure incurred therefore from the deposit such as Earnest Money, Security and Performance or other amounts available with TSTRANSCO or by resorting to legal action.

**23. PAYING AUTHORITY:** The Company shall submit the bills to the Superintending Engineer/OMC/ Nalgonda, who is the Paying Officer for the repairs of the subject Power Transformer after receipt of the repaired Power Transformer at the allotted substation, in good condition, duly certified by the consignee.

**24. JURISDICTION:** All the disputes arising out of this order shall be decided by a panel of arbitrators as follows.

Sl. No.	Value of claim	Panel of Arbitrators
i	Disputes involving amount up to Rs.10,000/- and below	Superintending Engineer of TSTRANSCO, Other than the circle to which dispute arises.
ii	Disputes involving amounts from Rs.10,000/- to Rs.50,000/-.	Any Chief Engineer of TSTRANSCO.
iii	There shall not be any reference of disputes for the value exceeding Rs.50,000.00 to arbitration. The parties shall approach the competent Civil Court having jurisdiction, if any such disputes arises.	

**25. PRESENCE OF YOUR ENGINEER AT THE TIME OF ERECTION:** The company has to depute company’s authorized Person/Engineer, at the time of erection, to ascertain any shortages of oil or any short supply of materials or unattended works, which are to be rectified at the place of allotment within one week of intimation.

**26. GENERAL:** All correspondence of general and technical nature shall be addressed to this office and Superintending Engineer/OMC/Nalgonda. Except where otherwise agreed to in this detailed order, all the Terms and Conditions stipulated in the Specification No. TST – 01/2017 is binding on the Company and they shall form part of this contract.

**27. ACKNOWLEDGEMENT:** Please acknowledge the receipt of this order with your confirmation of acceptance by you. The additional copy enclosed may please be returned with your signature in token of your acceptance.

Encl: As above

**Yours faithfully**  
**Sd/-**  
**Chief Engineer/Transmission (I/C)**

**WE ACCEPT THE TERMS AND CONDITIONS**

*Signature of the Repairer with*  
**date and seal of the company**

**Copy to the:**

- The Executive Director (Finance)/TSTRANSCO/Vidyut Soudha/Hyderabad.
- The Chief Engineer/Rural Zone/Hyderabad.
- The FA&CCA(Accounts)/ Vidyut Soudha/Hyderabad.
- The Superintending Engineer/OMC Circle /Nalgonda.
- The Superintending Engineer/QC & QA/Vidyut Soudha/Hyderabad
- The Divisional Engineer/MRT & Transformers/Nalgonda.
- The Divisional Engineer(T) to Director / Transmission)/TSTRANSCO/Vidyut Soudha/Hyderabad.
- The SAO(P&A) /TSTRANSCO/Vidyut Soudha/Hyderabad
- The SAO/Budget & Balance Sheet/ Vidyut Soudha/Hyderabad

Note: These orders are also available on TSTRANSCO website and can be accessed at the address [www.transco.telangana.gov.in](http://www.transco.telangana.gov.in)