

TRANSMISSION CORPORATION OF TELANGANA LIMITED

From :
Chief Engineer / 400kV
TSTRANSCO, Vidyut Soudha,
Hyderabad 500 082.
Tele Fax No : 040-2332 3933
EmailId:ce.400kv.vs@tstransco.in

To
M/s PVR Constructions,
Flat No. 301/B, H.No. 7-1-397/101,
Sri Sai Govardhan Kunj Apartment,
S.R. Nagar, Hyderabad-500038.
Phone: 040 – 23704370

P.O.No.677/OM-03/(SAP PO:5500000953)/CE/400kV/SE-I/D3-A1/HVWS/D.No:762/21
Dt: 30.12.2021.

Sir,

Sub: Supply, Erection, Testing and Commissioning of High Velocity Water Spray system (HVWS) Fire protection at Four (4) Nos. 500MVA ICTs i.e., 2 Nos. at Maheswaram SS, 1 No. at Shankarpalli SS and 1 No. at Gajwel SS on turnkey basis- **Detailed Supply Purchase Order** - Issued - Regarding.

Ref : 1. T.O.O(CE-400kV) Ms. No.1176, Dt:26.08.2021.
2. Lr.No.CE/400kV/SE-I/D3-A1/e-EHVT-02/2019-20/D.No.438/21,
Dt:02.09.2021.

-oOo-

I, acting for and on behalf of and by the order and direction of the TRANSMISSION CORPORATION OF TELANGANA LIMITED (herein after called 'TSTRANSCO') accept the M/s.PVR Constructions, Hyderabad, (here in after called 'Contractor') for Supply, Erection, Testing and Commissioning of High Velocity Water Spray system (HVWS) Fire protection at Four (4) Nos. 500MVA ICTs i.e., 2 Nos. at Maheswaram SS, 1 No. at Shankarpalli SS and 1 No. at Gajwel SS on turnkey basis for a total amount Rs.57,20,431.00 (Rupees Fifty Seven Lakhs Twenty Thousand Four Hundred and Thirty One only) as detailed in Schedule-A(i) to A(iii) enclosed, subject to the terms and conditions set out in this order.

1.0. SCOPE:

The Scope of this order covers Design, Engineering, Manufacturing, Testing before dispatch, Loading, Supply and unloading for destination including transportation, Insurance and storage of material equipment complete with accessories required for installation of High Velocity Water Spray system (HVWS) Fire protection at Four (4) Nos. 500MVA ICTs i.e., 2 Nos. at Maheswaram SS, 1 No. at Shankarpalli SS and 1 No. at Gajwel SS.

2.0 ABSTRACT OF SUPPLY PRICES:

ABSTRACT of Schedules: Schedule-A: Detailed schedule of prices and items is enclosed to the Purchase Order

Note: Detailed schedule of prices and items are issued with SAP part numbers. However, the item (material) description shall be as per schedules indicated in the **Bidding documents.**

Schedule –A:

Schedule of Supply of Equipment and Materials with Prices for

S. No.	Description	Total amount In Rs.
i.	Prices for Supply of material/equipment for 2 Nos. HVWS Fire protection system at 400/220kV Maheswaram SS	28,09,989.06
ii.	Prices for Supply of material/equipment for 1 No. HVWS Fire protection system at 400/220kV Shankarpally SS	14,34,135.40
iii.	Prices for Supply of material/equipment for 1 No. HVWS Fire protection system at 400/220kV Gajwel SS	14,76,306.97
	Grand Total : (Sch A(i) + A(iii))	57,20,431.43
	Or say	57,20,431.00
(Rupees. Fifty Seven Lakhs Twenty Thousand Four Hundred and Thirty One only)		

3.0 PRICES AND PRICE ADJUSTMENTS:

- 3.1 The Prices of Fire fighting equipment shall be **Firm** on all accounts such as increase in quantity of equipment / materials over that provided in the contract, execution of contract beyond the schedule completion period for whatever reasons, increase in the rates of material during and beyond the completion period etc. The prices indicated in Schedule-A(i) to A(iii) are FADS (Free at destination stores) including freight and insurance, relevant taxes & duties and other levies whatsoever.

Before offering the material from a Sub-Vendor (even though the company's name is indicated in the approved Sub-Vendors / Manufacturers list), the Contractor shall take prior approval of TSTRANSCO by submitting the credentials of the company, to meet the qualifying requirements.

Any bidder from a country which shares a land border with India will be eligible to bid any procurement whether of goods, services (including consultancy services and non – consultancy services) or works (including turnkey projects) only if the bidder is registered with the Competent Authority.

- 3.2 Quantities provided in the price schedules are provisional and payment will be limited to actual quantities based on the design and drawings approved by TSTRANSCO. Contractor shall complete the supplies, storage, erection, testing and commissioning, civil & construction works and other incidental services as per the system requirement and as stipulated in designs, drawings approved during the detailed engineering. The contract price adjustments will be made based on the actual required quantities utilized as per detailed engineering and as per completed quantities of the supplies.

- 3.3 **The tender percentage considered is 4.14% Less over the ECV of TSTRANSCO.**

4.0 TAXES AND DUTIES:

For supply of equipment & materials:

- 4.1 The FADS prices are inclusive of GST 18% (Over Ex works rate + Freight & Insurance). The Contractor is entirely responsible for payment of Taxes and duties, other local taxes or levies, license fee, etc., which are to be borne by him until the completion of the contract.
- 4.2 TSTRANSCO will not entertain any claim in relation to Taxes and other levies payable by the Contractor in respect of the transaction between the Contractor and their vendors/sub suppliers while procuring any components, subassemblies, raw materials equipment etc.
- 4.3 TSTRANSCO shall not bear any tax liability i.e., Income Tax, surcharge on Income Tax and any other Corporate Tax, irrespective of the mode of contracting. The contractor shall be liable and responsible for payment of taxes, under the provision of the law. The TSTRANSCO as per the respective acts will make deduction towards Income Tax, GST at source.
- 4.4 TSTRANSCO is registered under GST Act and Provisional ID is **36AAFCT0166J1Z9** CIN No.U40102TG2014SGC094248.

- 4.5 In case of interstate transactions made under IGST, the e-way bills will be processed in accordance with orders issued by the Government of India & Telangana. Necessary documents such as invoice, delivery challans, Order copies and any other documentary evidence mandated by Government for interstate movement of goods shall be produced by the contractors.

5.0 PAYMENT OF TAXES, LEVIES, DUTIES, STATUTES

- 5.1 Contractor shall be entirely responsible for payment of all taxes, levies, duties, other local taxes, license fees, etc incurred until delivery of the contracted goods to the TSTRANSCO.
- 5.2 The contractor shall pay all types of fees, levies, taxes, duties etc. required to be paid by any National or State statute, ordinance or other law or any regulation or bye-law of any local or other duly constituted authority in relation to the execution of works and by the rules and regulations of all Public bodies and companies whose property or rights are affected in any way during the execution of works. In compliance to the above, the contractor shall keep the Purchaser indemnified against all such penalties and liability of every kind for breach of any statute, ordinance or law, regulation or byelaw.
- 5.3 Nothing in the contract shall relieve the contractor from his responsibility to pay any tax that may be levied by the Government on the turnover / profits made by him in respect of the contract.

6.0 TAX AND CESS DEDUCTABLE AT SOURCE:

As per provision of Income tax Act, applicable Income tax, GST will be deducted at source at all stages of payment of the bills and same will be remitted to the concerned department as per the rules / acts of the State / Central Government.

The GST will be deducted in accordance with the orders issued by Government of India/Telangana from time to time at the rates, as applicable under TDS at all stages of payment of the bills and same will be remitted to the concerned department as per the rules / acts of the State / Central Government.

7.0 DELIVERY PERIOD:

The supply of materials and equipment shall be completed within Three(3) months from date of handing over of site.

8.0. TERMS OF PAYMENT:

The payment will be made through **TSTRANSCO Funds**.

8.1 For Supply (equipment/material):

- i) 80% payment will be made within 30 days for the material / equipment supplied and received in complete shape at destination stores / site in good condition (i.e. Check measurement date in Form - 13). The concerned AEE / 400kV/ Field will receive the equipment / material in full shape at site and the concerned EE/400kV / Field will do the check measurement and issue the Form-13. The check measurement shall be done within five days from the date of receipt of materials. The due date for payment will be reckoned from the date of check measurement mentioned in Form-13.
- ii) 10% payment will be made after erection of equipment / material.
- iii) Balance 10% payment will be made after commissioning of equipment / material

8.2 The bank account RTGS/NEFT details furnished by the company are as follows:-

S.No.	Particulars	Details
1	Beneficiary Name	M/s.PVR Constructions, Hyderabad
2	Beneficiary Office Address	Flat No. 301/B, H.No. 7-1-397/101, Sri Sai Govardhan Kunj Apartment, S.R. Nagar, Hyderabad-500038, Mb.No: 04023704370 Email: sudhakarkunta@pvrconstructions.com
3	Beneficiary's Bank Name	HDFC Bank
4	Beneficiary Bank Address	HDFC Bank Secunderabad, UshaKiran Complex, GR Floor, Paradise Circle, Sarojini Devi Road, Secunderabad, Telangana -500003
5	Beneficiary Bank Account No.	50200052061285
6	IFSC Code of the bank branch of the beneficiary for RTGS and NEFT Transfer	HDFC0000042
7	MICR No.	500240003

- 8.3 The payments are subject to submission of Performance Security with validity of Twelve (12) months with a further claim period of two months from the date of check measurement of materials/equipment.
- 8.4 If the contractor has received any over payments by mistake or if any amounts are due to the TSTRANSCO due to any other reason, when it is not possible to recover such amounts under the contract, TSTRANSCO reserves the right to collect the same from any other amount and / or Bank Guarantees given by the company due to or with the TSTRANSCO.
- 8.5 When the supplier/contractor does not at any time, fulfill his obligations in replacing / rectifying etc. of the damaged / defective materials in part or whole promptly to the satisfaction of the TSTRANSCO Officers, the TSTRANSCO reserves the right not to accept the bills against subsequent dispatches made by the supplier/contractor and only the supplier/contractor will be responsible for any demurrages, wharf ages or damage occurring to the consignments so dispatched.
- 8.6 The supplier has to furnish summary sheet of payment particulars with the details of item wise quantity supplied until the present consignment, quantity delivered in this consignment and balance to be delivered and corresponding amounts of payment.

The payment will be made to the Supplier under this Contract in Indian Rupees only.

The following documents specified below shall be submitted to the paying officer.

- a) Original for buyer invoice.
 - b) Delivery Challan Acknowledged by the consignee (S) (6 copies)
 - c) Insurance Certificate
 - d) Manufacturers/Suppliers Warranty Certificate
 - e) Approval of routine and Acceptance test reports.
 - f) 6 copies of packing list
 - g) Copy of Acceptance Letter of Performance Security issued by TSTRANSCO.
- 8.7 Where the Contractor requests for the payment in advance before the “scheduled date of payment” that would be examined by the Executive Director(Finance)/

TSTRANSCO to decide whether such facility could be extended or not and if found acceptable the Contractor should agree to offer a rebate/ discount @ 0.3% per week or part thereof for the advancement. Based on the decision, the Finance & Accounts wing will release priority payment to such Contractor after availing of the rebate/ discount.

9.0 PERFORMANCE SECURITY:

M/s.PVR Constructions, Hyderabad, has furnished the following 10% Bank Guarantee against Performance Security (Supply) for execution of subject project on turnkey basis.

S. No	BG No & Date	Amount in Rs.	Validity/Claim period	Type of BG
1.	BG No. 021GT02213160005, Dated: 12.11.2021	5,72,100/-	31.03.2023/ 30.03.2024	Performance security towards Supply

- i. The performance /Additional Performance Security shall cover the 12 months over and above completion period with a further claim period of two months from the date of check measurement of material / equipment.
- ii. The contractor has to furnish the requisite amendment for 10% of contract price and extend the validity of Bank Guarantee as and when requested by TSTRANSCO as per the provision of the contract.
- iii. TSTRANSCO will discharge the above bank guarantee after completion of the warranty/ Guarantee period as per the provisions of Contract.
- iv. In case of the non-execution of works within the stipulated completion period the Contractor shall extend the Bank Guarantee suitably to cover the 12 Months performance and 2 Months claim period from the expected date of commission of the project.
- v. In case of replacement/repair of any material/works after commissioning of the Sub-Station and before expiry of Guarantee / Warranty period, the contractor shall furnish separate bank guarantee valid for 12 Months with 2 Months claim period from the date of repair / replacement covering the value of such materials / works.

- vi. The Bank Guarantee for Performance Security should be extended suitably in case the equipment is found defective and not attended to within the performance guarantee period or any other contractual obligations are not fulfilled.
- vii. TSTRANSCO will discharge the Performance Security after completion of the contract and within 60 days of the expiry of the warranty.

10.0 CONTRACT AGREEMENT:

The written agreement to be entered into between the Chief Engineer / 400kV/ TSTRANSCO /Vidyut Soudha / Hyderabad and Contractor shall be the foundation of the rights and obligations of both the parties and the contract shall not be deemed to be completed until the agreement has first been signed by the Contractor and then by the officer authorized to enter into contract on behalf of the Transmission Corporation of TELANGANA Limited (or 'TSTRANSCO').

11.0 INSPECTION AND FACTORY TESTS:

- 11.1 The Engineer, his duly authorized representative and/or 3rd Party inspection agency acting on behalf of TSTRANSCO shall have at all reasonable times access to the Contractor's premises or Works and shall have the power at all reasonable times to inspect and examine the materials and workmanship of the Works during its manufacture or erection and if part of the Works is being manufactured or assembled at other premises or works, the Contractor shall obtain from TSTRANSCO and/or his duly authorized representative permission to inspect as if the works were manufactured or assembled on the Contractor's own premises or works. **TSTRANSCO reserves the right to witness any or all type (if any), acceptance and routine tests specified, for which at least 21 (twenty one) days' notice in advance shall be given by the Contractor. Contractor shall ensure before giving notices for type test that all drawings and quality plans have been got approved.** The equipment shall be dispatched to site only after approval of test certificates by TSTRANSCO.

In case of inspection of imported goods at the manufacturers premises all the costs towards local transport, accommodation etc. for two TSTRANSCO's Engineers including Inspection/Test Charges shall be borne by the contractor.

- 11.2 The Contractor shall give the TSTRANSCO twenty one (21) days' written notice of any material being ready for testing, for each stage of testing as identified in the approved quality plan and CIP. Such tests shall be to the Contractor's account except for the expenses of the Inspector. The TSTRANSCO/Inspector, unless witnessing of the tests is virtually waived, will attend such tests within thirty (30) days of the date of which the equipment is notified as being ready for test/inspection, failing which the Contractor may proceed with the test which shall be deemed to have been made in the Inspector's presence and he shall forthwith forward to the TSTRANSCO six copies of duly certified test reports.
- 11.3 The inspections and tests may be conducted on the premises of the Supplier or its subcontractor(s), at point of delivery and/or at the Good's final destination. Where conducted on the premises of the Supplier or its subcontractor(s), all reasonable facilities and assistance including access to drawings and production data shall be furnished to the inspectors at no charge to the TSTRANSCO. The contractor or his authorized quality person shall accompany the inspector from TSTRANSCO without fail at the time of inspection of material/ equipment /works at the sub vendor/contractor's works and shall sign on the inspection reports. The contractor shall dispatch the materials immediately after issuing dispatch instructions with test reports approval. In case of delay (more than one month), TSTRANSCO has every right to ask the contractor to re conduct the inspection and tests at free of cost due to the contractor's delay. The contractor shall offer all the materials/Equipment for inspection in full shape as per approved drawings/BOM. No part quantity will be accepted.
- 11.4 TSTRANSCO or Inspector shall, within fifteen (15) days from the date of inspection as defined herein give notice in writing to the Contractor, of any objection to any drawings and/or any equipment and workmanship which in his opinion is not in accordance with the Contract. The Contractor shall give due consideration to such objections and shall either make the modifications that may be necessary to meet the said objections or shall confirm in writing to TSTRANSCO giving reasons therein, that no modifications are necessary to comply with the Contract.

- 11.5 When the factory tests have been completed at the Contractor's or Sub-Contractor's works, TSTRANSCO shall issue a certificate to this effect within fifteen (15) days after completion of tests but if the tests are not witnessed by TSTRANSCO the certificate shall be issued within fifteen (15) days of receipt of the Contractor's Test certificate by TSTRANSCO. Failure of TSTRANSCO to issue such a certificate shall not prevent the Contractor from proceeding with the Works. The completion of these tests or the issue of the certificate shall not bind TSTRANSCO to accept the equipment, should it on further tests after erection, be found not to comply with the Contract.
- 11.6 Material being furnished against this order shall only be dispatched when factory inspection satisfactory to the TSTRANSCO and/or his representative has been conducted. Such inspection and acceptance for shipment shall not however, relieve the contractor from entire responsibility for furnishing Goods conforming to the requirement of this specification nor shall prejudice any claim, right or privilege which the TSTRANSCO may have, because of the use or supply of defective or unsatisfactory Goods. Should the TSTRANSCO waive the inspection, such waiver shall not also relieve the contractor in any way, from his entire obligations under this order.
- 11.7 In all cases where the contract provides for tests whether at the premises or works of the Contractor or of any Sub-Contractor, the Contractor except where otherwise specified shall provide free of charge such items as labour, materials, electricity, fuel water, stores, apparatus and instruments as maybe reasonably demanded by TSTRANSCO/Inspector or his authorized representative to carry out effectively such tests of the equipment in accordance with the Contract and shall give facilities to TSTRANSCO/Inspector or to his authorized representative to accomplish testing.
- 11.8 The Goods at factory or after installation shall be capable of performing satisfactorily and shall conform to the contractor's guaranteed Technical particulars. All tests required by this technical specification, including retests and inspection, that may be necessary owing to failure to meet any tests specified, shall be made at the contractor's expense. Additional tests, if necessary, shall be made to locate any such failure. After determining the cause of failure and rectifying it, specified tests

shall be repeated to establish that the rectified Goods conforms the specification in every respect. Should the Goods ultimately fail to pass the tests specified, the TSTRANSCO will have the option to reject the unit.

- 11.9 Should any inspected or tested Goods fail to conform to the Specifications, TSTRANSCO may reject them and the supplier/contractor shall either replace the rejected Goods or make all alterations necessary to meet specification requirements free of cost to the TSTRANSCO.
- 11.10 TSTRANSCO's right to inspect, test and, where necessary, reject the Goods after the Goods' arrival in TSTRANSCO's country shall in no way be limited or waived by reason of the Goods having previously been inspected, tested and passed by TSTRANSCO or its representative prior to the Goods' shipment from the country of origin.
- 11.11 The inspection by TSTRANSCO and issue of Inspection Certificate thereon shall in no way limit the liabilities and responsibilities of the Contractor in respect of the agreed quality assurance program.
- 11.12 Dispatch Instructions shall be issued by TSTRANSCO after inspection of the equipment. TSTRANSCO may waive off the presence of TSTRANSCO's inspecting engineer. In that case, test will be carried out as per approved QP & test certificate will be furnished by the Contractor for approval. D.I will be issued only after review & approval of the test reports.
- 11.13 TSTRANSCO will have the right to insist on any test(s) of reasonable nature carried out at Contractor's premises or at site or in any other place to satisfy that the material comply with the specification.
- 11.14 TSTRANSCO reserves the right for getting any field tests conducted on the completely assembled equipment at site.
- 11.15 The equipment offered shall be of type tested and shall be subjected to all routine and acceptance tests as per the relevant standards specified.

12.0 TYPE AND ROUTINE TESTS:

12.1 ROUTINE TESTS:

After completion of manufacture of the equipment routine tests shall be performed as per relevant standards and requisite copies of test certificates shall be furnished to TSTRANSCO.

Various components of the equipment shall be routine tested in accordance with approved standards and manufacturer's standards.

Each completely wired cubicles/Panels shall be tested to ensure that all of its protective control systems are satisfactorily functioning as required.

Six (6) copies of all test reports shall be submitted for approval before shipment of equipment. The Test Reports shall indicate clearly the standard values specified for each test, to facilitate checking of the test reports with comparison of the test results with the guaranteed requirements of the specifications, standards and explanation of deviations, if any.

13.0 PACKING AND MARKING.

13.1 The Contractor shall provide such packing of the goods as is required to prevent their damage or deterioration during transit to their final destination as indicated in the contract. The packing shall be sufficient to withstand without limitation, rough handling during transit and exposure to extreme temperatures, salt and precipitation during transit and open storage. Packing case size and weights shall take into considerations where appropriate, the remoteness of the goods final destination and the absence of heavy handling facilities at all points in transit.

13.2 The packing, marking and Documentation within and outside the packages shall comply strictly with such special requirements as shall be expressly provided for in the Contract.

13.3 In general each package shall be marked to indicate:

- a) Name of the Supplier
- b) Details of items in the package
- c) Name of the consignee
- d) Purchase order number
- e) Gross, net and tare weights of the items
- f) Destination.

- 13.4 Refer packing and marking of the Technical Specifications for further details. All the requisite documents as per specification for delivery of equipment and material shall be submitted.

14.0 TRANSPORTATION:

- 14.1 The Contractor is required under the contract to deliver the Goods free at Destination. Transport of goods to the destination, shall be arranged and paid for by the supplier, and the cost thereof shall be included in the contract price. It shall be the total responsibility of the Contractor to ascertain transportation limitations if any before the supplies.
- 14.2 Where the Contractor is required to effect delivery under any other terms, for example, by post or to another address, the supplier shall be required to meet all transport and storage expenses until delivery.
- 14.3 In all of the above cases, transportation of the goods after the delivery at destination Site/stores shall be the responsibility of the contractor unless specified otherwise.

15.0 INSURANCE:

- 15.1 The Goods supplied under the Contract shall be fully insured against loss or damage incidental to manufacture or acquisition, transportation and material supplied by TSTRANSCO should be insured against storage, delivery and erection. In case of domestic goods the insurance shall be at least for an **amount equal to 110% of the cost of the goods** from “warehouse to warehouse (final destination)” and **storage up to commissioning of goods** thereafter on “All Risks” basis including War Risks and Strike Clauses.
- 15.2 The Contractor shall arrange secure and maintain insurance as may be necessary and for all such amounts to protect the materials of the Purchaser against all risks till the Goods and services is taken over as detailed herein. The form and the limit of such insurance as defined herein together with the under writer thereof in each case shall be acceptable to the Purchaser. However irrespective of such acceptance the responsibility to maintain insurance at all times during the period of “Contract” shall be that of

contractor alone. The contractor's failure in this regard shall not relieve him of any of his contractual responsibilities and obligations.

- 15.3 The Contractor shall take Insurance cover in their name on behalf of TSTRANSCO. The above insurance shall be made in freely convertible currency. The contractor shall be responsible for preferring all claims and releasing the amounts from insurance. The scope of such insurance shall cover the entire value of the "Goods and Services".

Contractor shall

- a) **Initiate and pursue insurance claim till settlement and**
- b) **Promptly arrange for repair and / or replacement of any damaged items in full irrespective of settlement of insurance claim by the under writers.**

- 15.4 All costs on account of insurance liabilities covered under the contract will be on "Contractor's" account. The CONTRACTOR shall provide the Purchaser with a copy of all insurance policies and documents taken out by him in pursuance of the 'Contract'. Such copies of documents shall be submitted to the Purchaser immediately after such insurance coverage. The CONTRACTOR shall also inform the Purchaser in writing at least sixty (60) days in advance, regarding the expiry, cancellation and / or change in any of such documents and ensure revalidation / renewal etc., as may be necessary well in time. The Purchase shall assist the contractor if required in obtaining Licenses/port clearances, etc., in respect of foreign supply required for the purpose of replacement of Goods lost in transit. The risks that are to be covered under the insurance shall be comprehensive and shall include but not be limited to, the loss or damage in transit, storage, due to theft, pilferage, riot, civil commotion, weather conditions, accident of all kinds, fire, flood, war risk (during ocean transportation) bad or rough handling etc. The scope of such insurance shall cover the entire value of the 'Works'.

- 15.5 All costs on account of insurance liabilities covered under the 'Contract' will be on CONTRACTOR'S account and will be included in 'Contract Price'. **The insurance beneficiary shall be TSTRANSCO.**

Contractors are advised to claim the bills for Supplies / works and insurance separately. Insurance premiums will be paid only after getting confirmation from the Insurance companies. Wherever the bills are claimed combined, the insurance amount

will be excluded initially and paid only after getting the confirmation from the insurance companies, so that the main bills are paid without delay.

- 15.6 Comprehensive transport, storage, erection cum commissioning insurance.
- 15.7 All the equipment and materials being supplied by the Contractor shall be kept completely insured by the Contractor at his cost from the time of dispatch from the Contractors Works, upto the completion of erection, testing and commissioning at site and taking over the works by TSTRANSCO in accordance with the contract.
- 15.8 The Contractor shall inspect all the material received at destination store and furnish a loss/damage report to TSTRANSCO within a week of receipt of material at site, and provide all required assistance to TSTRANSCO in lodging insurance claims thereupon. In case of loss to TSTRANSCO due to delays in submitting the loss/damages report by the contractor, TSTRANSCO will be within his right to deduct such losses from the contractor's progressive payments.

All the equipment and materials being supplied by TSTRANSCO shall be kept insured by the contractor against loss, damage, theft, pilferage, fire etc., from the point of unloading up to the time of taking over of the works by TSTRANSCO including handling, transportation, storage, erection, testing and commissioning etc., and the contractor shall be fully responsible for making good of any loss or damage at his own cost. All costs for such insurance shall be to the contractor account and shall be deemed to be included in the contract price.

- 15.9 It will be the responsibility of the Contractor to lodge, pursue and settle all claims with the Insurance Company in case of any damage, loss, theft, pilferage or fire and the TSTRANSCO shall be kept informed about it. The losses, if any, will have to be borne by the Contractor, if the claims are not lodged and pursued properly or in time or if the same are not settled by the insurance company. The contractor shall replace the lost/damaged materials (own and the TSTRANSCO's supplied) promptly irrespective of the settlement of the claims by the underwriters and ensure that the work progress is as per agreed schedules. The losses, if any, in such replacement will have to be borne by the contractor.

16.0 DISPATCH INSTRUCTIONS:

The details of Consignee and Paying Officer for supply of equipment and materials are as follows. The equipment and materials covered in Schedule-A(i) to A(iii) shall be delivered to the site after getting approval from TSTRANSCO.

Sl. No.	Address for Despatch	Consignee	Paying officer.
1.	2 Nos. HVWS Fire protection system at 400/220kV Maheswaram SS	Executive Engineer/ 400kV/Const./Metro/ Hyderabad	Superintending Engineer/ 400kV/Const./ Metro/Hyderabad
	1 No. HVWS Fire protection system at 400/220kV Shankarpally SS		
	1 No. HVWS Fire protection system at 400/220kV Gajwel SS		

TSTRANSCO reserves the right to allot any surplus material from TSTRANSCO stores to project site and in such cases transportation charges will be given as per SSR Rates and the Contractor has to transport such material invariably and the balance quantity of material shall only be offered for supply.

17.0 VARIATION IN QUANTITIES:

The quantities indicated in the Schedule-A(i) to A (iii) (Materials / Equipment) are only provisional and are likely to change during actual execution.

18.0 TSTRANSCO RIGHT TO VARY THE SCOPE DURING THE PERIOD OF CONTRACT:

TSTRANSCO may change the scope of the contract based on the priorities and may subsequently extend for balance scope with the prices quoted if required.

TSTRANSCO reserves the right to increase or decrease the scope stated above as per requirement up to + or - 50% during the execution of the order with quoted prices.

18.1 SUPPLEMENTAL/NEW ITEMS AND PROCEDURE FOR WORKING OUT RATES

The contractor is bound to execute Supplemental / new items that are found essential, incidental and inevitable during execution of the contract at the rates to be worked out as below :-

For the items relating to Schedule-A (i) to (iii) where the rates of new items cannot be deduced from the estimate, the rate payable will be arrived based on the prevailing market rates duly enquiring / collecting quotations and observing the reasonableness of the rates by the TSTRANSCO.

The Schedule time required to complete the new / supplemental items including the balance work will be indicated in the approval letter issued for new / supplemental items.

The contractor shall plan and procure the materials indicated in Schedule –A(i) to A(iii) duly verifying with the approved layout and profile so that the procured quantities match with actual requirements to avoid excess supply of materials.

19.0 WARRANTY/GUARANTEE:

19.1 The Contractor shall guarantee, among other things the following:

- i. Quality and strength of materials / equipment used.
- ii. Adequate factors of safety for the material / equipment to withstand the mechanical and/or electrical stresses developed therein.
- iii. The delivery and erection periods.
- iv. The Contractor shall warrant further that the services to be carried out under this contract shall conform with generally accepted professional standards and engineering principles.
- v. The materials/ equipment supplied and erected shall be guaranteed for satisfactory operation for a minimum period of 12 months from the date of commissioning of project. By the time of completion of commissioning, Bank Guarantee for performance security and Bank Guarantee for final payment shall be valid to cover Guarantee/warranty period with claim period of two months.

However any Engineering error, omission, wrong provision, Goods failure etc., shall be attended to by the Contractor up to and on the date of actual Commissioning of the Goods without any revision in the price or extra cost.

- 19.2 If during the period of guarantee, any of the materials, are found defective and/or fail in test or operation, such materials, shall be repaired or replaced by the Contractor free of cost to the TSTRANSCO irrespective of the reimbursements from the insurance company within reasonable time which shall in no circumstance be more than 30 days or such other reasonable time as the TSTRANSCO may deem proper to afford failing which the cost of the failed material will be deducted from the subsequent bills/Bank Guarantee.
- 19.3 The contractor shall bear all the expenses incurred in connection with the repair or replacement against such defective Goods inclusive of all freight both inland overseas, insurance, customs levies, forwarding and clearing and demurrage and other incidental charges involved in delivering the said Goods to the Purchaser's specified destination. The decision whether correction of the defects should be by the repair or replacement shall be the sole discretion of TSTRANSCO.
- 19.4 Provision of this clause shall also apply to all materials and services repaired or replaced under the provision of this until the expiration of period of 12 (twelve) months from the date of such repair or replacement. In case of replacement/repair of any material/works after commissioning of the subject work and before expiry of Guarantee / Warranty period, the contractor shall furnish separate bank guarantee valid for 12 Months with 2 months claim period from the date of repair / replacement covering the value of such materials / works.
- 19.5 The cost of any special or general overhaul rendered necessary during the guarantee period due to defective Goods and Services furnished by the contractor shall be borne by the contractor.
- 19.6 The taking over of the Goods and services by the TSTRANSCO shall in no way relieve the contractor of his obligation under this clause.
- 19.7 The Contractor shall co-operate with the TSTRANSCO in all ways in repair or replacement of the defective part, so as to minimize to the extent possible the interruption in operation of Goods.

- 19.8 Where the sub-contractors provide longer periods of warranty than mentioned above, the TSTRANSCO shall be entitled for such longer guarantees.
- 19.9 If the Supplier/Contractor, having been notified, fails to remedy the defect(s) within a reasonable period, the TSTRANSCO may proceed to take such remedial action as may be necessary, at the Supplier's risk and expense and without prejudice to any other rights which the TSTRANSCO may have against the Supplier under the contract.
- 19.10 The Contractor's full and extreme liabilities under this clause shall be satisfied by the payments to the TSTRANSCO of the extra cost, of such replacement procured including erection as provided for in the contract, such extra cost being the ascertained difference between the price paid by the TSTRANSCO for such replacements and the contract price portion for such defective plants. Should the TSTRANSCO not so replace the defective plant, the contractor's extreme liability under this clause shall be limited to repayment of all sums paid by the TSTRANSCO under the contract for such defective plant.

20.0 PENALTY FOR LATE SUPPLIES:

The completion period mentioned in the Clause No.5 of this Order is the essence of contract. Penalty will be levied as follows for the delay in supply of material.

- (i) In case of delay in supply of material / equipment beyond over all delivery period, whatever may be the reasons, the TSTRANSCO shall levy and collect the penalty @ 0.5% per week of the delay on the delayed value of the material / equipment subject to a maximum of **10%** of the total value of the contract. Once the maximum is reached, TSTRANSCO shall consider termination of the contract.

The right of the TSTRANSCO to levy penalty shall be without prejudice to its rights under the law including the right to get the balance supplies from other agencies at the risk and cost of the Contractor. And also in case the Contractor fails to execute the supplies as per the program or in the opinion of TSTRANSCO, the supplies are progressing at a slow pace, TSTRANSCO reserves its right to get the balance supplies executed through other agencies at

the risk and cost of the Contractor. This is in addition to the right of the TSTRANSCO to forfeit the deposit, to recover any damage from the contractor and also blacklisting.

- (ii) The date of receipt of materials/equipment at the destination stores in good condition (The date of Check measurement in Form-13) will be taken as the date of delivery.

For penalty, the number of days of delay would be rounded off to the nearest week and interest calculated accordingly. Materials / equipment which are not of acceptable quality or are not conforming to specification would be deemed to be not delivered. The penalty specified shall be levied and would be adjusted against same bill / subsequent pending bills.

- (iii) Penalty shall be calculated while admitting the final bill, duly taking into account, extension of completion period if any, and the penalty shall be recovered along with applicable GST.
- (iv) However to ensure availability of sufficient amount for deducting penalty a recovery of 0.5% of the value of supply/work, delayed, per week (or part thereof, as the case may be) shall be adjusted against the Penalty (+GST) levied while admitting the final bill.

21.0 QUALITY ASSURANCE PROGRAMME:

21.1 To ensure that the equipment and services under the scope of this contract whether manufactured or performed within the Contractor's works or at his Subcontractor's premises or at the Purchaser's site or at any other place of work are in accordance with the specifications, the Contractor shall adopt suitable quality assurance program to control such activities at all points, necessary. Such program shall be outlined by the Contractor and shall be furnished as applicable. A quality assurance programme of the Contractor shall generally cover the following.

- a) His organization structure for the management and implementation of the proposed quality assurance programme;
- b) Documentation control systems;
- c) Qualification data for Contractors key personnel;

- d) The procedure for purchase of materials, parts, components and selection of Sub-Contractor's service including vendor analysis, source inspection, incoming raw material inspection, testing, verification of materials purchased, etc.
- e) System for shop manufacturing and site erection controls including process controls and fabrication and assembly controls;
- f) Control of nonconforming items and system for corrective actions;
- g) Inspection and test procedure both for manufacture and field activities
- h) Control of calibration and testing of measuring and testing equipment;
- i) System for indication and appraisal of inspection status
- j) System for quality audits;
- k) System for authorizing release of manufactured product to the Purchaser
- l) System for handling storage and delivery;
- m) System for maintenance of records; and
- n) A quality plan detailing out the specific quality control procedure adopted for controlling the quality characteristics relevant to each item of equipment/ component furnished.

The Contractor shall invariably furnish Quality Assurance Plan giving the following information. Information shall be separately given for individual type of equipment offered.

- i) Statement giving list of important raw materials, names of sub suppliers for the raw material, list of standards according to which the raw material are tested, list of tests normally carried out on raw material, copies of test certificates.
- ii) Information and copies of test certificates as in (i) above in respect of bought out items.
- iii) List of manufacturing facilities available.
- iv) Level of automation achieved and list of areas where manual processing exists.
- v) List of areas in manufacturing process, where stage inspections are normally carried out for quality control and details of such tests and inspections.

The material shall conform in all respects to high standards at engineering, design, workmanship latest revisions of relevant standards at the time of ordering and TSTRANSCO shall have the power to reject any work or material which in his judgment is not in full accordance therewith.

22.0 QUALITY ASSURANCE DOCUMENTS:

The Contractor shall be required to submit the following Quality Assurance Documents within before dispatch of the equipment.

- i) All Nondestructive Examination procedures, stress relief and weld repair procedure actually used during fabrication,
- ii) Welder and welding operator qualification certificates,
- iii) Welder identification lists, listing welders and welding operator's qualification procedure and welding identification symbols.
- iv) Material mill test reports on components as specified by the specification.
- v) The inspection plan with verification, inspection plan check points, verification sketches, if used, and methods used to verify that the inspection and testing points, in the inspection plan were performed satisfactorily.
- vi) Sketches and drawings used for indicating the method of trace ability of the radiographs to the location on the equipment
- vii) Non-destructive Examination result, reports including radiography interpretation reports.
- viii) Factory test results for testing required as per applicable codes and standards referred in the specification.
- ix) Inspection reports duly signed by Quality Assurance personnel of the TSTRANSCO and Contractor for the agreed inspection hold points. During the course of inspection, the following will also be recorded:
 - a) When some important repair work is involved to make the job acceptable; and
 - b) The repair work remains part of the accepted product quality.

23.0 DESIGN AND DRAWINGS

The Contractor shall design all the systems covered under the scope of this Purchase Order documents and obtain approval of all the design drawings duly indicating all the required bill of quantities (BOQ) on the A-1 Size drawing.

Soon after award of the contract, the Contractor shall furnish the list of drawings (equipment/material/erection) to be furnished by him in accordance with the specification as required for the scope of Supply, Erection & Commissioning.

- 23.1 Contractor shall submit for approval, as per the above schedule two sets of assembly drawing erection/construction and sufficient detailed drawings to demonstrate fully that the apparatus furnished and erection/construction work carried out shall conform to the provision and intent of these specifications. Detailed drawings or design data proving the adequacy of the Contractor's designs by calculations shall be submitted for approval by the TSTRANSCO.
- 23.2 The design data and the drawings submitted by the Contractor will be reviewed by the Purchaser as far as practicable within four (4) weeks of their receipt and shall be modified by the Contractor if any modifications and/or corrections are required by the TSTRANSCO. The Contractor shall incorporate such modifications and/or corrections and submit the final drawings for approval. Any delays arising out of failure by the Contractor to rectify the drawings in good time shall not alter the contract completion date.
- 23.3 When revised drawings are submitted for approval, the changes from the previous submittals shall be clearly identified on the drawings, with every revision made during the life of the contract shown by number, date and subject, in a revision block and a notation shall be given in the drawing margin. The drawings shall be clear and legible in all respects. The corrected and approved drawings shall be submitted both in Hard copies and Auto-CAD soft copies in three sets of CDs/Pen drives.
- 23.4 TSTRANSCO shall have the right to require the Contractor to make any changes in the design which may be necessary in the opinion of the TSTRANSCO to make equipment construction cum erection work conform to the provisions and intent of these specifications, without additional cost to the TSTRANSCO. One set of the drawings marked "APPROVED" will be returned to Contractor. He shall thereupon furnish the TSTRANSCO with ten sets of prints, soft copy in CD after incorporating all corrections.
- 23.5 Further work by the Contractor shall be in strict accordance with these drawings and no deviation shall be permitted without the written approval of the TSTRANSCO, if so required.

- 23.6 All manufacturing fabrication work and construction / erection in connection with the equipment before the approval of the drawings shall be at the Contractor's risk. The Contractor may make any changes in the design, which are necessary to make the equipment construction/erection conform to the provisions and intent of the contract and such changes will again be subject to approval by the TSTRANSCO.
- 23.7 Approval of drawings by the TSTRANSCO shall not be held to relieve the Contractor of any part of his obligation to meet all the requirements stipulated in the specification of responsibility for correctness.
- 23.8 One month prior to dispatch of the equipment final approved drawing sets, operation, maintenance and erection manuals shall be supplied to the TSTRANSCO in 6 copies. Also a soft copy of the drawings in Auto CAD version shall also be supplied.
- 23.9 The Contractor shall mark in red in one (1) set of drawings all deviations/alterations carried out at site during construction work. After final testing and commissioning, any corrections in the, field test, actual erection, testing and commissioning shall be incorporated in the drawings and the Contractor shall furnish to TSTRANSCO ten (10) copies of the revised drawings/manuals and marked as "As Built" drawings shall be supplied in the Office of the Chief Engineer/400kV /Vidyut Soudha /Hyderabad. However, no alternations/deviations shall be carried out without the prior approval of the TSTRANSCO.
- 23.10 The Contractor shall also furnish two sets of reproducible along with soft copy in CD/pen drive of all reference drawings and documents/designs after approval and two sets of reproducible of all as built drawings as certified by the field engineer of TSTRANSCO.
- 23.11 Drawings shall include all installation and detailed piping drawings. All piping 100 millimeter and larger shall be routed in detail and smaller pipe shall be shown schematically or by isometric drawings.
- 23.12 Each drawing shall be complete with Bill of Materials and legends. It shall contain technical requirements of quality assurance to be observed at shop and technical requirements for work at site like welding length, weld size, type of electrodes etc.

24.0 INSTRUCTION MANUALS & STANDARDS:

The Contractor shall submit to TSTRANSCO instruction manuals for all equipment to be supplied against this Order covering technical details, erection procedures, testing, operation and maintenance including troubleshooting. Each manual shall also include a complete set of approved drawings together with performance/rating curves of the equipment and test certificates wherever applicable. The 'Contract' shall not be considered to be completed for purposes of taking over until such instruction manuals and drawings have been supplied to TSTRANSCO. The manuals shall be submitted in 12 copies duly incorporating the comments after review by TSTRANSCO on the model manuals to be submitted by the Contractor.

A separate section of the manual shall be for each size / type of equipment and shall contain a detailed description of construction and operation, together with all relevant pamphlets, drawings and a list of parts with procedure for ordering spares. Maintenance instructions shall include charts showing lubrication checking, testing and replacement procedures to be carried out daily, weekly, monthly and at longer intervals to ensure trouble free operation.

Where applicable, fault location charts shall be included to facilitate finding the cause of mal-operation or breakdown. A collection of the manufacturer's standard leaflets will not be accepted, to be taken as a compliance of this clause. The manual shall be specifically compiled for the concerned project.

25.0 SURPLUS MATERIALS:

On completion of works, all the surplus material which has been already billed by contractor to TSTRANSCO but not used by contractor in the project, shall be handed over designated TSTRANSCO stores at the cost of the contractor within the time limit of 2 months of commissioning of the project. However if the material is not handed over within such time limit or in the opinion of designate officer of TSTRANSCO who is in-charge of the works, such material is not in fit condition for use, such material shall be retained by the contractor and recovery shall be made from contractor at the rate as per the contract rate.

In exceptional cases, in order to expedite work progress, whenever TSTRANSCO issues the material from its stores on returnable basis to the contractor, the contractor shall return such material within 30 days from the date of issue of such material along with interest on the value of such material at the rate of 2% per month or part thereof.

However if contractor fails to return material within 30 days of issue of such material, the material shall be deemed to have been sold to contractor on the date of its issue to contractor at a price which shall be 150% of the procurement cost and such cost shall be recovered from contractor along with interest at 2% per month or part thereof from the date of issue of material till amount is recovered.

26.0 TERMINATION OF CONTRACT:

The TSTRANSCO may, without prejudice to any other remedy for breach of contract, by written notice of default sent to the supplier/ Contractor, terminate the contract in whole or in part:

- a) If the supplier/Contractor fails to deliver any or all of the goods and to complete any or all works commensurate with progress of completion within the time period(s) specified in the contract or any extension thereof granted by the TSTRANSCO.
- b) If the supplier/Contractor fails to perform any other obligation(s) under the contract.
- c) If the supplier/Contractor, in the judgment of the TSTRANSCO has engaged in corrupt or fraudulent practices in competing for or in executing the contract.

Termination of contract:

If it is found that supplies and progress of works are not commensurate with the program of completion or if the contractor does not fulfill his obligations as per the terms of the specification TSTRANSCO will be entitled to terminate the contract in part or full by giving 15 days notice and get the balance works completed through other agencies at the contractor's cost and risk.

Warning letters will be issued by the TSTRANSCO if the progress is not satisfactory. If the progress continues to be poor even after the second warning letter, show cause notice/final notice will be issued by the Chief Engineer/400kV. If no satisfactory reply is received or the progress of the works are not improved within 15 days of issue of the final notice/show cause notice, the Chief Engineer / 400kV shall terminate the agreement, which will be followed by stoppage of all payments to the contractor, encashment of the BGs, and after termination of contract the balance works/supplies shall be completed through alternate agencies at contractor's risk and cost. **The contractor so penalized shall be blacklisted for 3 years from the date of termination of contract.**

In the event of termination of contract due to delay attributable to the contractor, TSTRANSCO is entitled to get back equipment/material from the contractor for the payment already made but the material is not put to use, and then get the works done by other agency/agencies for completion of contract by using the said recovered material. The contractor shall have no objection in this regard.

However, the Supplier /Contractor shall continue performance of the Contract to the extent not terminated.

27.0 APPLICABLE LAW & JURISDICTION:

All and any disputes or differences arising out of or touching this Order shall be decided by courts or tribunals situated in Hyderabad / Secunderabad cities only. No suit or other legal proceedings shall be instituted elsewhere.

28.0 CORRESPONDENCE:

All the correspondence regarding the technical matters /works / payments and other field matters shall be addressed to the Superintending Engineer/400kV/ Construction /TSTRANSCO/Metro/Hyderabad with copies marked to this office.

29.0 GENERAL CONDITIONS OF CONTRACT:

Except it is provided otherwise in this contract, all the general, technical, commercial terms and conditions stipulated in the specification for this contract shall be complied with.

30.0 DETAILS OF ENCLOSURES:

The following are the enclosures to this order, which form part of the contract.

1. Appendix-A
2. Schedule of Prices - A (i) to A (iii).

Please note that all terms & conditions of Specification e-EHVT-02/2019-20 unaltered will form part of this Order.

Yours faithfully,

CHIEF ENGINEER/ 400kV
(For and on behalf of TSTRANSCO)

Copy to be returned to TSTRANSCO by the Contractor duly signed on every page of this order in acknowledgement and acceptance of this order.

We accept the terms and conditions of this order.

SIGNATURE OF THE CONTRACTOR.

Copy to:

1. Executive Director (Finance)/TSTRANSCO/Vidyut Soudha.
2. Chief Engineer/Civil/TSTRANSCO/Vidyut Soudha.
3. Superintending Engineer/400kV/Const./Metro/Hyderabad.
4. Superintending Engineer/Civil/400kV/Projects/Vidyut Soudha.
5. Executive Engineer/ 400kV/Const./Metro/Hyderabad.
6. DE (T) to Director (Projects)/TSTRANSCO/Vidyut Soudha.
7. SAO/P&A/TSTRANSCO/Vidyut Soudha/Hyderabad.
8. AO, O/o. Superintending Engineer/400kV/Const./Metro/Hyderabad.

Appendix-A**SUPPLY**

P.O.No.677/OM-03/(SAP PO:5500000953)/CE/400kV/SE-I/D3-A1/HVWS/D.No:762/21
,Dt: 30.12.2021.

1. For the Supply of equipment and materials the final list of manufacturers / sub vendors shall be submitted, chosen from the list mentioned in the specification. The final list of sub vendors will be as per the approved list of TSTRANSCO / Power Grid for their substations. The type test reports, technical particulars for all these equipment and materials shall be submitted by M/s.PVR Constructions, Hyderabad and get the approval of TSTRANSCO before procurement action is initiated.
2. M/s.PVR Constructions, Hyderabad., will furnish the detailed programme in the form of Master Net work for Supply to meet the completion Schedule as stipulated.
3. The TSTRANSCO has the option to reduce / increase the scope of supply as required for the final system requirement and as per approved design and drawings during the execution of the contract at the prices quoted.
4. All the equipment offered will be of type tested and in the absence of valid relevant type test reports, these type tests will be conducted at no extra cost to the TSTRANSCO.
5. Two copies of all the relevant Standards along with latest amendments, applicable for the equipment and material covered in the order shall be provided by the Contractor at free of cost to TSTRANSCO during Engineering.
7. All the design calculations, Drawings, Bill of materials for the equipment & works covered in the scope of the contract shall be furnished to TSTRANSCO, in a soft copy also, at no extra cost during Engineering.
8. M/s.PVR Constructions, Hyderabad., shall take delivery of certain equipment and material allocated available elsewhere at TSTRANSCO stores / sites required for 400kV Sub-station as directed by TSTRANSCO and in such cases transportation charges will be given as per SSR Rates and the Contractor has to transport such materials invariably.

Fire Protection, Detection, & Alarm Systems:

9. The quantities are purely tentative. Contractor shall design the system as per the specification and execute the same as per the approved drawings.

10. The payments will be based on actual quantities as per approved drawings. Price adjustment for the size / capacity of the items which are not indicated will be done as per the price for nearest lower size / capacity of the item of this schedule.
11. Any other item required for completion of the system as per specification is deemed to have been included in this schedule.
12. MS Pipe prices are for ERW pipes to API-5L GRB above 150NB and carbon steel pipe heavy class black for the pipes of 150NB and below as per IS: 3589 and IS: 1239 with anti-corrosion treatment.
13. 'Set' mentioned above include total number of equipment to be covered therein including the standby equipment to meet the requirement as per specification .
14. Fire Protection, Detection & Alarm System shall be erected as per the Tariff Advisory Committee standards and regulations for getting maximum permissible rebates in fire insurance premium. The contractor shall obtain approval of the system by TAC also.

Chief Engineer / 400kV